CCTV Engineering Report

Executive Summary: Project Objectives, Scope, Key Findings, and Separation of Requirements from Recommendations

This report establishes the engineering basis for a CCTV system covering architecture, cameras, network infrastructure, video management, storage and retention, cybersecurity, and testing and commissioning. Its objective is to define a coherent, supportable, and secure video surveillance solution while providing sufficient technical detail for design development, procurement, installation, configuration, acceptance, and operational handover. The report is intended to support informed decisions by the project owner, designer, integrator, information-technology team, and security operations personnel.

The scope includes the principal system components and their interfaces: cameras and mounting arrangements; power and data connectivity; switching and transmission networks; video management and monitoring functions; recording, storage, retention, backup, and export; user access and cybersecurity controls; and inspection, testing, training, and documentation. It also addresses practical design matters such as environmental suitability, image quality, coverage objectives, bandwidth, PoE loading, resilience, access control, system maintainability, and future expansion. Detailed site-specific quantities, camera locations, field-of-view diagrams, retention periods, network addressing, rack layouts, and equipment schedules remain subject to approved project information and coordinated design documentation.

No project drawings, risk assessment, operational brief, asset inventory, performance test results, or approved technical schedules were provided for this report. Accordingly, this executive summary does not assert verified site conditions, achieved performance, compliance status, or final equipment selections. The key finding at this stage is that the CCTV solution must be developed as an integrated system rather than as a collection of cameras. Camera performance depends on mounting, illumination, scene activity, network capacity, recording configuration, storage availability, cybersecurity, and operational procedures. These dependencies should be resolved through coordinated design review and validated during commissioning.

Project-specific requirements are mandatory obligations established by the owner, contract, applicable legislation, authority requirements, approved security objectives, and formally accepted design documents. They should be recorded in a traceable requirements schedule and verified through inspection, configuration review, testing, and handover evidence. Recommendations in this report are engineering guidance intended to improve reliability, image usability, security, maintainability, and lifecycle value. Recommendations do not replace contractual requirements and should be adopted only after confirming compatibility with the project brief, existing infrastructure, budget, and stakeholder approvals.

Where information is incomplete, the report identifies the matter as requiring confirmation rather than assuming a value. Before procurement or installation, the project team should approve the coverage and performance objectives, confirm interfaces with enterprise networks and access-control systems, establish retention and privacy requirements, validate resilience expectations, and agree acceptance criteria. Subsequent sections provide the technical framework for completing those decisions and separating confirmed requirements from design recommendations.

System Architecture: CCTV Topology, Functional Components, Integration Points, Resilience, and Project-Specific Design Requirements

2. System Architecture: CCTV Topology, Functional Components, Integration Points, Resilience, and Project-Specific Design Requirements

The CCTV system should use a structured, managed architecture in which cameras connect to access-layer network switches, with video transported over dedicated or logically separated network segments to the Video Management System (VMS). The VMS should provide recording, live monitoring, event management, user administration, audit logging, and controlled access to recorded footage. Operator workstations, investigation clients, display systems, and approved remote-access services should connect to the VMS through authenticated

application services rather than directly to cameras wherever practical. This topology supports centralized policy enforcement, simplifies administration, and limits exposure of camera devices.

Core functional components comprise fixed and movable cameras, mounting hardware, local power or Power over Ethernet (PoE), network switches, fiber or copper uplinks, the VMS application and database services, recording servers or appliances, storage systems, operator workstations, display controllers, time synchronization services, and system management tools. Ancillary components may include uninterruptible power supplies, environmental enclosures, surge protection, equipment racks, and dedicated maintenance interfaces. Camera selection and quantities should be based on the required fields of view, identification objectives, lighting conditions, privacy constraints, and operational procedures established for the project.

Integration points should be defined through controlled interfaces and documented data flows. Potential integrations include access control events, intrusion detection, intercoms, perimeter sensors, building management systems, identity services, email or notification platforms, and security information and event management systems. Integration should specify the event source, trigger conditions, exchanged data, time synchronization method, failure behavior, and ownership of configuration. Open standards or documented application programming interfaces should be preferred to reduce dependency on undocumented vendor functionality.

Resilience should address both equipment failure and loss of supporting services. Recommended measures include redundant recording or management components where operational risk justifies them, resilient network uplinks, protected power supplies, health monitoring, configuration backup, and defined degraded-operation behavior. The design should state whether cameras continue recording during temporary VMS, network, or site-server outages and how footage is recovered or reconciled afterward. Critical equipment should be located in secure, ventilated areas with controlled access and appropriate environmental protection.

Project-specific requirements shall be confirmed before detailed design and procurement. These include the coverage boundary, security zones, camera mounting constraints, required identification and detection outcomes, recording schedules, retention obligations, control-room operating model, remote viewing permissions, interfaces to existing systems, available power and communications infrastructure, resilience targets, privacy requirements, and applicable approval processes. Recommendations should remain subject to site survey, risk assessment, stakeholder approval, and compatibility testing with existing infrastructure.

Camera Specifications: Camera Types, Resolution, Optics, Mounting, Environmental Ratings, Analytics, and Selection Recommendations

Camera selection shall be based on the operational purpose of each viewing position rather than on a single camera model throughout the site. Project-specific requirements should define the areas requiring identification, recognition, detection, general observation, evidential recording, or situational awareness. These requirements should also identify lighting conditions, expected subject distance and movement, privacy constraints, vandalism risk, and any need for continuous or event-based monitoring.

Fixed dome and fixed bullet cameras are generally suitable for routine indoor and outdoor coverage. Domes provide a discreet appearance and can offer improved protection against tampering, while bullets may provide more practical long-range infrared illumination and visible deterrence. Pan-tilt-zoom cameras should be treated as supplementary devices for live assessment, perimeter observation, or following incidents; they should not replace fixed cameras where continuous coverage or evidential recording is required. Multi-sensor cameras may reduce mounting points in wide areas, but their cost, bandwidth, storage demand, and installation complexity should be assessed against separate fixed cameras.

Resolution shall be selected with reference to the required image detail at the target area, not simply the camera’s nominal pixel count. Higher resolution can support identification across wider scenes, but performance also depends on pixel density, lens selection, lighting, compression, camera processing, and subject movement. The design should avoid excessive wide-angle coverage where faces or number plates become too small for the intended task. Wide dynamic range is recommended for entrances, loading areas, and other locations exposed to backlighting. Low-light performance, infrared capability, and control of infrared reflection should be evaluated for night-time scenes. Where colour identification is important, cameras designed for low-light colour operation may be preferable to relying solely on monochrome infrared images.

Optics shall be matched to each scene through a documented field-of-view assessment. Varifocal lenses are recommended where final framing may change during installation, while motorised lenses can simplify remote adjustment and commissioning. Camera height and orientation should limit glare, sky exposure, blind spots, and unintended views into neighbouring or private areas. Mounting hardware shall be appropriate to the substrate and loading conditions, with concealed or protected cabling where tampering is a concern.

Outdoor equipment should have environmental and impact ratings appropriate to the location, including protection from dust, water, condensation, corrosion, temperature variation, and mechanical attack. Exact ratings should be confirmed against site conditions and manufacturer documentation rather than assumed. Analytics such as line crossing, intrusion detection, loitering, object classification, and tamper alerts may improve operational response, but they require scene-specific configuration and validation to limit nuisance alarms. Recommended cameras should therefore be selected through a coverage schedule identifying model characteristics, mounting position, viewing objective, lighting condition, environmental exposure, analytics, and recording profile for every device.

Network Infrastructure: Bandwidth, PoE, VLANs, Switching, Connectivity, Quality of Service, Redundancy, and Network Requirements

The CCTV network should be designed as a dedicated, managed IP infrastructure that provides sufficient capacity for live viewing, recording, administration, analytics, and system expansion. Required bandwidth shall be calculated from the final camera count, resolution, frame rate, compression method, scene activity, and recording mode. Calculations should include peak concurrent traffic rather than relying solely on average bit rates. Allowance should also be made for protocol overhead, multicast or unicast viewing, maintenance access, and future camera additions. The network shall not be dimensioned only for camera-to-switch traffic; uplinks to the video management system, recording servers, storage, and remote monitoring locations must also be assessed.

Power over Ethernet (PoE) shall be provided for compatible cameras and associated devices using switches that comply with the applicable IEEE PoE standard and support the required per-port and total power budget. The budget shall account for camera heaters, infrared illuminators, motorized lenses, pan-tilt-zoom operation, microphones, and other connected accessories where applicable. Switch selection shall consider startup and peak power demand, operating temperature, available spare capacity, and the effect of a switch or power-supply failure. PoE ports should be individually monitored, with remote disable and restart capability where supported.

Camera traffic should be separated from corporate, guest, voice, building-management, and other operational traffic by implementing a dedicated CCTV VLAN or appropriately segmented VLANs. Inter-VLAN routing shall be restricted to necessary services, such as video management, time synchronization, directory services, monitoring, and authorized administration. Default gateway, DHCP, DNS, and addressing arrangements shall be documented. Static addressing or DHCP reservations are recommended for cameras, recording servers, switches, and other critical components to simplify identification and recovery.

Managed switches shall provide sufficient port density, non-blocking switching capacity, buffer performance, and uplink bandwidth for the connected devices. Uplinks should use redundant paths or link aggregation where supported and justified by the architecture. Switches serving critical cameras should be connected to resilient power, with uninterruptible power supplies sized for the required ride-through period. Network equipment shall be installed in secure, ventilated locations and protected against unauthorized physical access.

Quality of Service should prioritize control, management, and time-sensitive video traffic where congestion could affect operation, while avoiding configurations that unnecessarily disrupt recording. Multicast should be used only where the VMS and network design support it reliably; otherwise, unicast bandwidth requirements shall be included. Time synchronization is required across cameras, servers, switches, and supporting systems to maintain accurate event correlation.

The final design shall document bandwidth calculations, PoE budgets, VLANs, IP addressing, routing rules, switch schedules, uplink capacities, power resilience, and connectivity dependencies. Recommendations for redundancy, spare capacity, and remote connectivity shall be confirmed against the project’s availability, cybersecurity, and operational requirements before implementation.

Video Management System: Platform Functions, User Roles, Recording and Monitoring Workflows, Integrations, Licensing, and Configuration Recommendation

The Video Management System (VMS) shall provide centralized management of live video, recorded footage, alarms, users, devices, system health, and investigative workflows. The selected platform should support the proposed camera protocols and features, including ONVIF interoperability where applicable, while preserving reliable access to manufacturer-specific functions such as analytics, metadata, audio, inputs, outputs, and edge recording. The VMS shall be scalable to accommodate the final camera quantity, recording resolution, frame rate, retention policy, and future expansion without requiring fundamental platform replacement.

User access shall be governed by role-based permissions and the principle of least privilege. Typical roles include system administrators, security supervisors, control-room operators, investigators, maintenance personnel, and read-only or audit users. Permissions should be assignable by site, camera group, live viewing, playback, export, alarm acknowledgement, configuration, and user administration. Administrative actions, logins, exports, evidence access, and configuration changes shall be recorded in an auditable event log. Where the project infrastructure supports it, authentication should integrate with the organization’s directory service and, for privileged accounts, multi-factor authentication.

The primary monitoring workflow should present operators with configurable layouts, camera maps, alarm queues, health indicators, and priority views. Operators should be able to acknowledge alarms, display associated cameras, control supported PTZ devices, add bookmarks or incident notes, and escalate events according to site procedures. Recorded video shall be searchable by time, camera, event, motion, analytics metadata, and operator bookmark, subject to the capabilities of the selected cameras and VMS. Exported evidence should include a secure, tamper-evident format with an integral player or documented playback method, time and date information, camera identification, and an export audit trail.

Recording workflows shall support continuous, scheduled, event-driven, and pre-/post-alarm recording as required by the approved operational concept. The VMS should provide recording-server failover, device health monitoring, storage-status alerts, and controlled recovery following network or power interruptions. Camera time synchronization shall use the project’s approved time source so that events can be correlated across CCTV, access control, intrusion detection, and other systems.

Integration requirements shall be confirmed during detailed design. Likely interfaces include access-control events, intrusion alarms, intercoms, building-management systems, video walls, analytics platforms, and a central monitoring or incident-management system. Interfaces should use supported, documented methods and define ownership for alarms, acknowledgements, data exchange, and failure handling.

Licensing shall be assessed for camera channels, recording servers, failover, analytics, mobile access, integrations, concurrent users, and software support. The recommendation is to select a commercially supported, open-protocol VMS with transparent recurring costs, documented upgrade compatibility, and sufficient capacity for approved expansion. Final licensing quantities and configuration shall be based on the issued camera schedule, retention requirements, integration matrix, and cybersecurity policies.

Storage and Retention: Recording Modes, Capacity Calculations, Retention Policies, Redundancy, Backup, Archiving, and Storage Requirements

Storage capacity shall be designed from the camera schedule, recording mode, resolution, frame rate, compression standard, scene activity, and required retention period. Capacity calculations shall use the aggregate recording bitrate rather than nominal camera count alone. A preliminary calculation may be expressed as:

Required capacity (TB) = [total bitrate (Mb/s) × 86,400 × retention days] ÷ [8 × 1,000,000]

An engineering allowance shall then be added for filesystem overhead, metadata, audio where applicable, variable bitrate peaks, database growth, and operational free space. The final design shall validate the

calculation against the selected VMS, recording server, storage platform, and manufacturer performance limits. Storage sizing shall be based on documented camera profiles and shall be recalculated whenever camera quantities, recording settings, or retention requirements change.

The required recording mode shall be assigned by camera priority and operational purpose. Continuous recording is recommended for evidentially important views, entrances, perimeter areas, cash-handling locations, and other areas where events may not trigger analytics reliably. Motion- or analytics-based recording may be appropriate for lower-risk areas where storage reduction is required, provided detection performance is tested and pre-event and post-event recording buffers are configured. Critical cameras should retain continuous recording even when analytics are enabled. Recording profiles should define resolution, frame rate, bitrate control, keyframe interval, audio policy, and schedules for normal, reduced-activity, and maintenance periods.

Project-specific requirements shall define the minimum retention period for recorded video, the cameras subject to that period, and any legal, contractual, or operational hold requirements. Retention shall be implemented through controlled VMS policies rather than manual deletion. The system shall prevent recording gaps caused by full storage and shall provide alerts for capacity thresholds, disk faults, recording interruptions, and abnormal retention behavior. Time synchronization shall be maintained across cameras, recording servers, and storage systems to preserve evidential value.

Redundancy shall be selected according to the operational consequence of storage failure. A fault-tolerant disk arrangement, such as an appropriate RAID or equivalent distributed-storage scheme, is recommended, but redundancy shall not be treated as a substitute for backup. Recording servers should support failover or redundant recording for designated critical cameras where uninterrupted evidence capture is required. The design shall document failure modes, expected recovery procedures, rebuild impacts, and remaining usable capacity after a disk failure.

Backup requirements shall distinguish operational recording from long-term evidence preservation. Routine backups should protect VMS configuration, user settings, licenses, databases, and system documentation. Exported video shall preserve the original evidence, timestamps, audit information, and an approved playback method, with access restricted and export activity logged. Long-term archives shall use controlled storage with integrity verification, environmental protection, lifecycle management, and documented destruction authorization. Storage locations shall provide adequate power, cooling, physical security, monitoring, and expansion capacity for the planned system lifecycle.

Cybersecurity: Hardening, Authentication, Access Control, Encryption, Patch Management, Monitoring, Incident Response, and Security Recommendations

The CCTV system shall be treated as a security-critical information system. Cybersecurity controls shall apply to cameras, encoders, network switches, wireless links where used, recording servers, storage platforms, operator workstations, mobile clients, management software, and all interfaces to external or enterprise systems. Devices shall be hardened before connection to the production network, with unnecessary services, default accounts, unused interfaces, legacy protocols, and insecure remote-access functions disabled. Configuration backups shall be protected and maintained under controlled change management.

Authentication shall use unique named accounts rather than shared credentials. Strong password requirements, account lockout or throttling, session timeouts, and secure credential storage shall be enabled. Multi-factor authentication is recommended for administrators, remote users, and any account capable of changing system configuration or accessing sensitive recordings. Privileges shall follow least-privilege principles, with separate roles for system administration, security management, live viewing, playback, export, and audit review. Access to cameras and recordings shall be restricted by site, role, time, and operational need. Administrative actions, login events, failed access attempts, video exports, configuration changes, and deletion activity shall be logged and retained in accordance with applicable policy.

Encryption shall be enabled for management traffic, user authentication, remote viewing, and integrations wherever supported. Secure protocols shall replace unencrypted services, and certificates shall be issued, monitored, renewed, and revoked through an approved process. Recorded video and exported evidence shall be protected at rest using platform-supported encryption or encrypted storage. Exported files shall include

appropriate integrity protection, access restrictions, and chain-of-custody records.

Firmware, operating systems, VMS applications, databases, and network equipment shall be maintained through a documented patch-management process. Assets and software versions shall be inventoried, vendor security advisories reviewed, and updates risk-assessed before deployment. Critical security updates shall be prioritized, with maintenance windows, rollback procedures, configuration backups, and post-update verification. Unsupported products shall not be introduced, and replacement plans shall be established for components that reach end of support.

Monitoring shall include device availability, storage health, recording status, time synchronization, authentication events, configuration changes, abnormal traffic, and loss of camera connectivity. Alerts shall be sent to designated personnel or a security monitoring platform, with defined severity levels and escalation paths. System clocks shall use an approved, authenticated time source to support reliable event correlation.

An incident-response procedure shall define identification, containment, evidence preservation, recovery, notification, and lessons-learned activities. Compromised accounts or devices shall be isolated without unnecessarily destroying evidence. Recovery procedures shall be tested periodically, including restoration of configurations and access to required recordings.

Project-specific cybersecurity requirements shall be confirmed during detailed design, including network segmentation, remote-access approval, retention of audit logs, and integration boundaries. As recommendations, the project should use a dedicated CCTV VLAN, restrict management access through controlled administration networks, conduct vulnerability assessment before acceptance, and provide cybersecurity and incident-response training to operators and administrators.

Testing and Commissioning: Inspection, Configuration Verification, Performance Testing, Acceptance Criteria, Documentation, Training, Handover, and Ou

8. Testing and Commissioning: Inspection, Configuration Verification, Performance Testing, Acceptance Criteria, Documentation, Training, Handover, and Ongoing Support

Commissioning shall verify that the CCTV installation is complete, safe, correctly configured, and capable of meeting the approved design intent. Inspection shall cover camera mounting, field of view, focus, image orientation, protective housings, cable routing, labeling, earthing, PoE availability, switch connections, equipment-room conditions, and physical protection of all devices. Any deviations from drawings, schedules, or approved equipment selections shall be recorded and resolved or formally accepted before handover.

Configuration verification shall confirm device naming, time synchronization, firmware versions, IP addressing, VLAN assignment, recording profiles, frame rates, resolution, compression, retention settings, analytics, privacy masks, user roles, alarm rules, and system integrations. Camera views shall be checked against the approved coverage plan, including critical entrances, perimeters, access points, and operational areas. Default credentials shall be removed, administrative access restricted, and cybersecurity hardening completed in accordance with the approved security requirements.

Performance testing shall be conducted under representative operating conditions. Tests should include live viewing, recording, playback, export, search, authentication, alarm generation, camera disconnection and restoration, network interruption, storage failover where provided, time synchronization, and operation from designated client workstations and mobile or remote interfaces. Image quality shall be assessed for identification, recognition, and general observation objectives as applicable. Analytics shall be tested using representative events while documenting false alarms, missed detections, environmental limitations, and any required tuning. Testing shall not be considered complete until corrective actions have been retested and closed.

Acceptance criteria shall be defined before testing and aligned with the approved drawings, equipment schedules, functional requirements, cybersecurity requirements, and applicable authority or client standards. At minimum, acceptance should require complete device inventory, correct camera coverage, stable recording, successful retrieval and export of evidential video, accurate timestamps, functioning alarms and integrations,

compliant user access, and no unresolved critical defects. Where project-specific values such as retention duration, image performance, recovery time, or availability have not been stated, they shall be agreed and documented rather than assumed.

The commissioning dossier shall include approved drawings, as-built topology and cable schedules, asset and IP-address registers, configuration backups, test scripts and signed results, defect and closeout records, licenses, warranties, firmware records, cybersecurity settings, maintenance procedures, and supplier contact details. Training shall be provided to operators, supervisors, and administrators and shall include live monitoring, investigations, evidence export, alarm handling, user management, routine checks, and escalation procedures.

Handover shall occur only after documentation, training, spares, keys, passwords, and support arrangements have been transferred under controlled procedures. The recommended ongoing-support plan includes preventive maintenance, periodic camera cleaning and image-quality checks, backup verification, patch review, storage-capacity monitoring, access reviews, and periodic recommissioning after significant configuration, network, or software changes.